

## Projects needed at Fossil Rim Wildlife Center



<b>The Lodge</b>	
Repave lodge entrance road	12 feet wide Chip and Tar approximately 17500 square FT total
Repair wooden fence around the lodge	Remove existing boards. Landscape fence area Install 2 6X6 posts per section Rework existing boards and replace broken boards. 20 sections in total. Paint boards and posts brown.
Water well	Replace water storage tank Install iron filter and re-plumb. Repair pump house and roof
Lodge entrance.	Build foundation for new cattle guard.
	Supply and install new cattle guard.
	Supply and install motorized decorative gate with fittings with electronic key pad.
	Replace 8 feet high game fence
	Landscape area
Water leak from outside to front office through concrete wall.	Dig out foundation, seal line, install french drain and re-sculpt. Remove equipment from closet, cut drain, epoxy foundation cracks. Install sump pump.
Ceiling repair in passage way	Repair water damage to ceiling on 2nd floor in passage. Remove ceiling replace with new drywall and paint
Repair water damage in lounge area	Remove wood floor and carpet in lounge/bar area – prepare and stain floor.

<b><u>Foothills Safari Camp</u></b>	
Board walks, decking and outdoor furniture	Remove dirt around decking to expose timber step areas. Replace broken boards, Repair bridge. Clean and re-seal all boards and outdoor furniture.
Water feature	Remove rock and old lining. Rework stream and pond area reline and replace rocks. Build filter system and install pump and plumbing.
Pathways	Lay new cedar crossties. Fill with decomposed granite and spray with polymer
Garden area	Remove cedar logs between parking area and lawn Trim trees and landscape areas.
Doors	Sand, clean and re-seal tent and pavilion doors
Tent shade netting	Replace shade net on all tents. Extend new net 4' more on the front than existing net. Replace cedar post frameworks for netting as necessary
<b><u>Admin Building</u></b>	
East Wing	Construct new office in foyer of admin building
<b><u>Horticulture Center</u></b>	
Clean up building surrounds	Clean area. Remove vegetation and landscape area to include parking area for 4 vehicles
Remodel building	Install a concrete slab
	Repair cedar building. Frame one new inside wall with door. Install 2 window AC units
<b><u>Katie's Cottage</u></b>	
Roof	Replace roof with composite shingle roof
<b><u>Wolf Ridge Camp</u></b>	
	Install cement ADA ramps at cabins, Eco center & Children's Animal Center. 9 in total
<b><u>Overlook Area</u></b>	
Overlook Café	Temporary repairs to foundation
Parking area	Repair wooden rails in parking area
Upgrade existing Nature Store toilets	Strip and stain floors
	Remove redundant fittings and repair walls
	Replace toilet fittings with new.
	Fit 4 hand dryers. Including electrical connections
	Refurbish existing doors with closers
	Reframe and move door in female section to new position
	Clean & re-grout tiles
	Supply and fit new toilet

	Supply and install new partitions
	Install new baby changing stations
	Prepare and paint restrooms
<b>Animal Facilities</b>	
APC Incubation center	Construct new 45 X 50 building (Drawings will be available end of July)
	Supply and install standby Generator
White Rhino Barn	Add pipe fencing and weld in place
	Repair walls and paint
Cheetah	Repair wooden fencing
	Supply 15 wooden dens as per specifications
Holding Pens	Repair and replace wooden fencing as necessary.